



# SONAMARG DEVELOPMENT AUTHORITY

Tel/Fax: - 0194-2416100( Ganderbal) Email:-Sdaofficial@yahoo.com

## CORRIGENDUN

Reference:-This office e-NIT No. 01 of 2017-18 Dated: 21-4-2017 issued vide this office No EE/SDA/ 19-22 Dated: 21-04-2017

Pl read unit of item No 24, 26,27,31,32, 34 and 36 as under:-

S.No	Description of Item	Unit	Instead of
24	P/F track deck crill make or equivalent H.I rib profiled sheets 1000 to 1020mm cover width 28-35mm high crests at 250 to 255mm TCT (total coated thickness) high tensile SMP Galvalume steel. The sheets shall have wide panes with 3 No. stiffing ribs, effective water shedding and special male/female ends with fuil return legs on side laps for purlins support and anti-capillary flute inside lapp. The sheets shall have a hot dip metallic coated of zinc and aluminum (150 gms/sm) zinc/aluminum coating mass total on both side AZ-150 as IS-1397,550 PMA, yield stress. Providing silicon modified polyester coating of approved colour of total thickness of 35 micron comprising 20 micron exterior coat of SMP over 5 micron polyester back coat over 5 micron primer coats on both surfaces incld. side and end lap and using 8mm galvalume hex self drilling fastener on each crest of sheet for connection with purlins and seam bolts at 300mm centers on all side and end lapps etc. including ridges / valleys (measured for unit of laid area).50mm	Sm	Cft
26	P/F of wooden eaves boarding (size 32x230mm) of approved pattern & design of 2nd. Class kail wood.	Rm	Sm
27	P/F paneled or paneled and glazed shutters for doors, windows & clerestory windows including ISI marked black enameled M.S pressed butt hinges bright finished of required size with necessary screws including cost of 20mm thick panels for doors, all complete as per direction of Engineer-in-charge.(1st class kail wood) 35mm thick.	Sm	Rm
31	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position.(First class budloo wood)	Cft	Sm
32	P/F of 12 mm thick Nordic Pine wall paneling (T&G) fully finished & four sides planned, fungus and termite proof (seasoned moisture content 8% to 15% imported type ISO :14001 approved including fixing with head less nails and inclusive all carriages, all taxes of allied material involved complete. (Including buloo wood frame work,12mm thick ply wood )including providing & applying two or more coats of touch wood polishing complete in all respects.	Sm	Cft

34	15 mm cement plaster 1:3 ( 1 cement : 3 coarse sand ) finished with a floating coat of neat cement on the rough side of single or half brick wall including all carriages / head load upto site of work complete.	Sm	Rm
35	P/L vitrified floor Antiskid tiles (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. <ul style="list-style-type: none"> <li>• (Size of 60x60 Cm)</li> </ul>	Sm	(Size of 60x60 Cm)

Sd/-  
Executive Engineer,  
Sonamarg Development Authority

No:-EE/SDA/26-29.  
Dated:27/04/2017.

Copy to:-

01. Chief Executive Officer Sonamarg Development Authority for information.
02. Joint Director, Information Department, and Kashmir province for publication in two leading dailies of Kashmir Province.
03. Notice Board.